

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-065-02696-00-01

RECEIVED
STATE CORPORATION COMMISSION

OCT 28 1963
10-28-1963
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name John O. Farmer, Inc.,
Complete Address: 370 West Wichita, Russell, Kansas.
Lease Name Benoit Well No. 1
Location SE-SE-NW Sec. 24 Twp. 8 Rge. (E) (W) 22
County Graham Total Depth 3748
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Comstock Pipe Pulling, Inc.,
Address: Stafford, Kansas. License No. 490
Operation Completed: Hour 10:00AM Day 23 Month 10 Year 1963

The Above well was plugged as follows:

155'--8 5/8" Surface Pipe, cement circulated.
3747--4 1/2" cemented with 100 Sx. Well plugged back to 3460'. Top of per-
forations @ 3426'. Top of cement @ 3370' (Temp. Survey).
Sanded well back to 3410' and set 2 Sx cement with dump bailer. Pulled
4 1/2" to 600', circulated heavy gel mud and displaced 20 Sx cement thru 4 1/2",
Pulled 4 1/2" to 150', and displaced 20 Sx cement thru 4 1/2". Pulled 4 1/2",
@ 35'
set bridge and 10 Sx cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 10/29/63

INV. NO. 4992-W

Signed: M. L. Nichols
Well Plugging Supervisor