

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20262-00-00

RECEIVED
STATE CORPORATION COMMISSION
SEP 29 1969
CONSERVATION DIVISION
Wichita, Kansas

9-29-69

Operator's Full Name Imperial Oil Company,
Complete Address 780 Fourth National Bank Building, Wichita, Kansas.
Lease Name Fink Well No. C-1
Location CSE-NE Sec. 21 Twp. 8 Rge. (E) (W) 22
County Graham Total Depth 3600'
Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X
Other well as hereafter indicated _____
Plugging Contractor Above
Address _____ License No. _____
Operation Completed: Hour 3:00 AM Day 25 Month 9 Year 1969

The above well was plugged as follows:

209'--8 5/8" Surface casing, cement circulated with 185 Sx.
Top of Dakota section @ 725'.

Circulated hole with heavy mud. Pulled DP to 900' and displaced 100 Sx. cement thru
DP from 900' to 575'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from 215'
to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/29/69
INV. NO. 546-4

Signed: W. L. Nichols
Well Plugging Supervisor