

SP

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-065-20462-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 6 - 1971  
CONSERVATION DIVISION  
Wichita, Kansas

7-6-71

Operator's Full Name Dreiling Oil, Incorporated,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Dunwoody Well No. 1

Location CNE-NW Sec. 21 Twp. 8 Rge. (E) (W) 22

County Graham Total Depth 3620'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Above

Address        License No.       

Operation Completed: Hour 5:30 PM Day 29 Month 6 Year 1971

The above well was plugged as follows:

172'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 650'.

Circulated hole with heavy mud. Pulled DP to 875' and displaced 100 Sx. cement thru  
DP from 875' to 550'. Pulled DP to 185' and displaced 25 Sx. cement thru DP from  
185' to 110'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7-7-71

INV. NO. 3935-W

Signed: N. L. Nichols  
Well Plugging Supervisor