

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

06-25-1970  
RECEIVED  
STATE CORPORATION COMMISSION  
JUN 25 1970  
CONSERVATION DIVISION  
Wichita, Kansas

15-065-20220-00-00

Operator's Full Name Shields Oil Producers,

Complete Address Shields Building, Russell, Kansas.

Lease Name Smith Estate Well No. A-1

Location NW-NW-SE Sec. 23 Twp. 8 Rge. (E) (W) 22

County Graham Total Depth 3740

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Forbes Casing Pulling Company, Incorporated,

Address Box #211, Great Bend, Kansas. License No. 49

Operation Completed: Hour 1:30 PM Day 22 Month 6 Year 1970

The above well was plugged as follows:

200'--8 5/8" Surface casing, cement circulated with 175 Sx.  
3630'--5 1/2" casing cemented on bottom with 75 Sx. Well Plugged back to 3619'. Top perforations from 3580' to 3584'. Top of cement @ 3150'--(Temperature Survey).  
Sanded well back to 3525' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing and squeezed well initially with 5 sacks hulls and 10 Sx. gel and followed with 100 Sx. cement from 1025' to 700', then 12 sacks gel from 700' to 220' and followed with 25 Sx. cement from 220' to 145' then 3 sacks gel from 145' to 25' and finally 10 Sx. cement from 25' to bottom of cellar. Maximum pump-in pressure--1000#. Final shut-in pressure-300#. (Mudding and cementing operations by Halliburton).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols  
Well Plugging Supervisor

DATE 6/25/70  
INV. NO. 2116-W