

DISTRICT CONSERVATION AGENT'S REPORT

*R*

15-065-00354-00-00

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NW NW SW

SEC. 24 TWP. 8 RGE. 22 W

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Gosselin

Operator A. E. Keating Address 510 Natl Bk Tulsa Bldg

Field \_\_\_\_\_ County Graham *Wilson, Okla*

Total Depth 3749 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 196' circulated with cement - 5 1/2" at ~~2400~~' 3530'

Perforated at 3460'.

Filled with chat to 3450', set 5 sax cement with dump bailer,

pulled 2400' 5 1/2", filled hole with mud to 196', set rock

and 15 sax cement, mud to 35', set rock and 10 sax cement

to bottom cellar.

**PLUGGING**  
FILE SEC 24 T 8 R 22 W  
BOOK PAGE 54 LINE 2

10-22-1952  
OCT 22 1952

*[Signature]*  
District Conservation Agent

CONSERVATION DIVISION  
Wichita, Kansas

Date 10-21-52