

KANSAS

4

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20228-00-00

RECEIVED
STATE CORPORATION COMMISSION
06-02-1969
JUN 2 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Shields Oil Producers, Incorporated,

Complete Address Shields Building, Russell, Kansas.

Lease Name Gosselin Well No. A-1

Location NE-SE Sec. 24 Twp. 8 Rge. (E) (W) 22

County Graham Total Depth 3695'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Shields Drilling Company, Incorporated,

Address Shields Building, Russell, Kansas. License No. _____

Operation Completed: Hour 10:30 PM Day 30 Month 5 Year 1969

The above well was plugged as follows:

200'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 600'.

Circulated hole with heavy mud. Pulled DP to 805' and displaced 100 Sx. cement thru
DP from 805' to 480'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from
215' to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/3/69

INV. NO. 9876-4

Signed: W. L. Nichols
Well Plugging Supervisor