

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

DEC 11 1973
12-11-1973
CONSERVATION DIVISION
Wichita, Kansas

15-065 - 20642-00-00

Operator's Full Name Petroleum, Inc.

Complete Address 300 W. Douglas, Wichita, Kansas

Lease Name Gosselin "B" Well No. 1

Location NW SE SW Sec. 24 Twp. 8 Rge. (E) (W) 22

County Graham Total Depth 3600'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Murfin Drilling

Address Wichita, Kansas License No.

Operation Completed: Hour 6 P Day 9 Month 12 Year 1973

The above well was plugged as follows:

RTD 3600' 8 5/8 csg set at 246' cwc 150 sk. Cem. Mat. 50-50 poz W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sk
cem thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cem
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Lee J. Messer
Well Plugging Supervisor

DATE 12/11/73

INV. NO. 8282-10