

KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING SUPERVISOR'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

15-065-00521-00-00<sup>01</sup>

File No. \_\_\_\_\_ Location: SW SW SW  
County: Graham Sec. 28 Twp. 8 Rge. 22 (E) (W)   
Name of Field or Pool: \_\_\_\_\_ Total Depth: 3710

I have this date completed supervision of plugging of:

Well No. #1 Lease MOORE

Operator's Full Name IMPERIAL OIL OF KANSAS, Inc.

Complete Address: 780 Fourth Nat Bldg - Wichita, Ks.

Plugging Contractor: SOUTH-WEST CASING PULLING CO.

Address: GREAT BEND, Ks. License No. \_\_\_\_\_

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

If well is a rotary drilled dry hole did operators wait for you to arrive \_\_\_\_\_

If yes how long \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 12 Noon Day 12 Month MAY Year 1958

The above well was plugged as follows:

TOP PERFORATION 3504' SANDED BACK TO 3488'  
ROCK BRIDGE + 4 SX CEMENT BY DUMP BAILER  
MUDDED BACK TO 210' ROCK BRIDGE + 25 SX  
CEMENT. MUDDED BACK TO 40' ROCK BRIDGE  
+ 10 SX CEMENT TO BASE OF CELLAR. RECOVERED  
APPROX 2600' OF 4 1/2" CASING. 228' OF 8 5/8" SURFACE.

I hereby certify that the above well was plugged as herein stated and that I was present while the above well was being plugged.

Signed: A. D. Fabian  
Well Plugging Supervisor

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Rec'd 05-29-1958

Reviewed: J. Lewis Brock  
Field Supervisor

Signed: \_\_\_\_\_  
Well Plugging Supervisor

Remarks:

