

15-065-00280-00-00

Form CP-3
Rev. 6-4-68

KANSAS

2 STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 24 1971
CONSERVATION DIVISION
Wichita, Kansas
May 24, 1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name John O. Farmer, Incorporated,
Complete Address Box #352, Russell, Kansas.
Lease Name Mickelson Well No. A-1
Location NW-NW-SE Sec. 27 Twp. 8 Rge. (E) (W) 22
County Graham Total Depth 3775'
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated _____
Plugging Contractor Ralph Comstock Pipe Pulling, Incorporated,
Address 320 South Park Stafford, Kansas. License No. 490
Operation Completed: Hour 11:45 AM Day 20 Month 5 Year 1971

The above well was plugged as follows:

165'--8 5/8" Surface casing, cement circulated.
3762'--5 1/2" Production casing cemented on bottom. No plug back nor perforations indicated.
Pushed plug to 3300', sanded well back to 3275' and set 5 Sx. cement with dump bailer.
Pulled 5 1/2" casing and squeezed well initially with 4 sacks hulls and 10 Sx gel and followed with 90 Sx. cement from 950' to 650' then 10 Sx. gel from 650' to 250' and followed with 1 sack hulls from 250' to 200' and finally 60 Sx. cement from 200' to bottom of cellar. Maximum pump-in pressure-150#. Final shut-in pressure-100#.
(Mudding and cementing operations by Allied Cementing Co., Inc.).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. Nichols*
Well Plugging Supervisor

DATE 5-24-71
INV. NO. 3736-W