

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-21,593-00-00

LEASE NAME Higer

WELL NUMBER # 2

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

Ft. from S Section Line
NE/1NE/4 NE/4
Ft. from E Section Line

LEASE OPERATOR Vicorp Energy Inc.

SEC. 19 TWP. 8s RGE. 23w (#) or (W)

ADDRESS 6200 S. Syracuse Way, Englewood, Colorado 80111 Suite 125 COUNTY Graham

PHONE# 303) 796-0990 OPERATORS LICENSE NO. 7632

Date Well Completed 3-1-82

Character of Well D&A

Plugging Commenced 7-3-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7-10-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? no if not, is well log attached? sent log with CP-1

Producing Formation ? Depth to Top _____ Bottom _____ T.D. 3765

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	229	8 5/8		
		0	3764	4 1/2		1600

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Fill with sand to 3625 & dump 4 sxs. cement.
Pump from surface 32 sxs. gel with 2 sxs. hulls mixed in & 100 sxs. cement with 1 hull mixed in then 8 sxs. gel, then 1 85/8 plug & 70 sxs. cement.
Used 60/40 poz-mix 6% gel & 3% c.c. cement.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Nicholas Casing Pulling License No. 6698

Address 420 5th. Geneseo, Ks. 67111

STATE OF Kansas COUNTY OF Rice, ss.


Allen D. Nicholas (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) Allen D. Nicholas

(Address) _____

SUBSCRIBED AND SWORN TO before me this 12 day of July, 19 85
STATE CORPORATION COMMISSION
7/15/85
Steven K. Prickett
Notary Public

My Commission Expires: JUL 15



CONSERVATION DIVISION
Wichita, Kansas