


15-065-02328-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

~~Trego~~ GRAHAM County, Sec. 20 Twp. 8S Rge. 23W(E) (W)

Location as "NE/CNW&SW&" or footage from lines NW NW SW

Lease Owner Imperial Oil of Kansas, Inc.

Lease Name Kobler Well No. 1

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed February 5, 1957

Application for plugging filed April 6, 1957

Application for plugging approved April 6, 1957

Plugging commenced April 6, 1957

Plugging completed April 6, 1957

Reason for abandonment of well or producing formation No commercial quantities of oil found.

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3774 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with crushed rock to 3700',
dumped 4 sacks cement with dump bailer,
at 3700', top of cement 3275'. Filled
hole with mud to 180', set rock bridge,
dumped 20 sacks cement. Top of cement,
120'. Filled hole with mud to 30', set
rock bridge, dumped 10 sacks cement for
cap.

RECEIVED
STATE CORPORATION COMMISSION

APR 17 1957

4/17/57

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Miller Casing Pulling Company
Address P. O. Box 711, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Raymond L. Bacon (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) By: Raymond L. Bacon V.P.
903 Union National Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of April, 19 57

My commission expires December 19, 1960

Louetta M. Duncan
Louetta M. Duncan
Notary Public.

PLUGGING
FILE SEC 20 T. 8 R. 23W
BOOK PAGE 4 LINE 37

15-065-02328-00-00

DRILLER'S LOG

Imperial Oil of Kansas, Inc.
903 Union National Building
Wichita 2, Kansas

Kobler No. 1
NW NW SW Sec. 20-8S-23W
Graham County, Kansas

Total Depth: 3774'

Commenced: 1-13-57 Completed: 2-5-57

Elevation: 2215' R.B.
Production: D & A

Contractor: Imperial Oil of Kansas, Inc.
Wichita 2, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 187' with 150 sacks cement.

Figures indicate bottom of formations:

Sand & Clay	40'			
Shale & Shells	1425'			
Shale & Sand	1550'	Anhydrite	1905'	(-310)
Shale & Red Bed	1790'	Heebner	3525'	(-1310)
Sand, Shale & Red Bed	1905'	Toronto	3546'	(-1331)
Anhydrite	1945'	Lansing	3565'	(-1350)
Shale & Shells	2620'	Total Depth	3774'	(-1559)
Shale & Lime	3175'			
Lime	3353'			
Lime & Shale	3510'			
Lime	3774'			
Total Depth	3774'			

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: Ray L. ...
Vice-President

Subscribed and sworn to before me this 22nd day of February, 1957.

My Commission Expires:

December 19, 1960

RECEIVED 4/17/57
STATE CORPORATE COMMISSION

Notary Public

APR 17 1957

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING		
FILE	SEC. 20	T. 8 R. 23W
BOOK	PAGE 4	LINE 37