

15-173-00796-00-00

R

2 060235

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- old well 1929
NW~~N~~ENW, SEC. 14, T 26 S, R 2 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 8965

330 feet from N/S section line
appr. 600 feet from W/E section line

Operator: Stekol Petroleum Inc.

Lease Name Rose Hamant Well # 2
12CC 2110 #25WD

Name & Address Wichita, KS

County Sedgwick 130.26

Ray Stekol

Well Total Depth 4008 feet

Conductor Pipe: Size 7" feet 3484 ✓
~~XXXXXXXXXX~~ 2 1/2" Liner 3414

Surface Casing: Size 16" feet 200 - 200 Sk

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated Arbuckle

Plugging Contractor United Cement License Number _____

Address El Dorado, KS

Company to plug at: Hour: _____ Day: 9 Month: 11 Year: 19 85

Plugging proposal received from Ray Stekol

(company name) _____ (phone) _____

were: Well had 16" surface pipe 200 cement all 7" casing at 3484 - cement for 1650'

4 1/2" liner at 3414 on packer squeezed to surface. Run wire line to check hole -

pump 50 sacks cement - check fillup- run 1" down 4 1/2" 300' fill cement. cut swedge run

1" between 7" - 16" and circulate full cement for 300'. Weld plate--fill cellar

Plugging Proposal Received by Ron Wilson
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 10:00a.m. Day: 19 Month: 3 Year: 19 85

ACTUAL PLUGGING REPORT Ran flag to T.D. 3950' no casing holes. Displaced 50 sacks of
common cement, 3%cc, 1/4# flo seal. Let set 2 hours--Ran flag on wire line fill up 3600'

Hooked pump truck could still pump into disposal zone. United pumped another 150 sacks

1/4 lb. flo seal displaced to 2700". Waited 2 hours ran wire line. Tagged cement fill

up at 3245' (Cont.)

Remarks: Ticket 8146 Ticket #7191 Ticket #10302

(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION

I (did / ~~did not~~) observe this plugging. 3/26/85

INVOICED

DATE 4-11-85

MAR 26 1985

Signed Ron Wilson
(TECHNICIAN)

INV. NO. 7574

CONSERVATION DIVISION
Wichita, Kansas

RO

- 3-18-85 Ran flag with wire line 2 times down 4½". Bridge and hole at approximately 2500'. Pumped 250 sacks of common 3% cement through hole to surface-between surface pipe and casing. Cement circulated. Let set.
- 3-19-85 Ran wire line between 16" and 7" - cement fell 85' - Ran wire line in 4½" cement at 85' - Evident casing parted during operation. Cement equalized ~~in~~ 4½" and casing-surface pipe annulus. Ran flag hole at approximately 83'. Hooked to 4½" and circulated 100 sacks down 4½" and out annulus to surface. Shut in. Let set one hour fell approximately 10 feet. Filled annulus and bottom of pit with approximately 24 more sacks of common cement. Pit was being pumped during operation.

No Drilling Intent

Drilled 1929