

2 090043

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 173-20,446-00-00  
NWSWNE, SEC. 3, T. 26 S, R. 2 XXE  
\_\_\_\_\_ feet from N/S section line  
\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5684

Lease Name Erdwien Well # "C"

Operator: George Sage

County Sedgwick

Name & Address Box 2

Well Total Depth 3330 108.23 feet

Virgil, Ks.

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8" feet 206'

Abandoned Oil Well XX Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Long Drilling License Number 6112

Address Box 131, Hamilton, Ks.

Company to plug at: Hour: \_\_\_\_\_ Day: 27 Month: 8 Year: 19 84

Plugging proposal received from \_\_\_\_\_

(company name) \_\_\_\_\_ (phone) \_\_\_\_\_

were: sand back to 2836' 5 sacks; top bridge 250 4yds.  
4 1/2" 2610'

RECEIVED  
STATE CORPORATION COMMISSION  
9-5-84  
SEP 05 1984  
CONSERVATION DIVISION  
WICHITA, KANSAS  
(TECHNICIAN)

\_\_\_\_\_ Plugging Proposal Received by \_\_\_\_\_ (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part XX None \_\_\_\_\_

Operations Completed: Hour: 5:00p.m. Day: 27 Month: 8 Year: 19 84

ACTUAL PLUGGING REPORT The bottom of the hole was filled with sand to 2836' and 5 sacks

of cement were spotted on top of the sand through the bailer. The pipe was shot off and 2610' of 4 1/2" was recovered. The top was plugged by setting a wood and rock bridge at 250' and dumping 4 yards of redi-mix to surface.

Remarks: Knebler Ticket #16275  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
I (and/or my representative) observe this plugging.

DATE 9-7-84

Signed David Wertz (TECHNICIAN) RO

INV. NO. 3561

9-27