

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-19026-00-01
Spot: SWSWSW Sec/Twnshp/Rge: 2-19S-11W
330 feet from S Section Line, 330 feet from W Section Line
Lease Name: KLEPPER Well #: 1-W
County: BARTON Total Vertical Depth: 3370 feet

Operator License No.: 32826
Op Name: MICHAELIS, ROGER DBA ALEO OIL CO
Address: 1864 NW 20 AVE
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	8.625	168		
PROD	3.5	3296	0	75 SX
SURF	5.5	3270	0	

109.53

Well Type: EOR UIC Docket No: _____ Date/Time to Plug: 01/24/2008 9:00 AM
Plug Co. License No.: 32528 Plug Co. Name: FUNK, DAVID A. DBA OIL AND OPERATING SERVICES
Proposal Rcvd. from: DAVE FUNK Company: ALEO OIL COMPANY Phone: (785) 324-1041

Proposed
Plugging
Method:

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/24/2008 2:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perforated at 3050'.
Pressured casing to 1700 P.S.I. - no rate.
Perfed at 2450' - pumped 125 sxs 60/40 pozmix - 4% gel cement.
Displaced cement to 600'.
Perfed at 600' - circulated up backside with 160 sxs cement.

Note: No Docket Number with well record.

Perfs:

Top	Bot	Thru	Comments
3224	3228		

INVOICED

DATE 2-4-08
INV. NO. 2008061153

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 30 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OILWELL CEMENTING.

Plugged through: CSG

District: 04

Handwritten initials

Signed _____

Handwritten signature: Case Morris

(TECHNICIAN)

JAN 28 2008

Handwritten initials

9-101, Map No. _____ O W W O
 OPER GRAYBOL OIL CORP., Tulsa, Okla.
 WELL #1 KLEPPER POOL UNIT
 CONTR Co. Tools
 FIELD Klepper (Lans oil)
 I.P. Water Inj. Well (Lans 3220-28) (OA)

	2	

S-T-R 2-19S-11W
 SPOT SW SW SW
 CO BARTON (Ks)
 ELEV 1779 KB

(KB Spl's:)

Anh	570 /1209
Hb	2914 -1135
BL	3030 -1251
Lans	* 3049 -1270
Cg	3354 -1575
RTD	3370 -1591

OLD INFO: (Was Ben Hyde, Jr., Et al) #1 Klepper)
 DST #1 (Lans) 3131-41, Op ¼ hr, R 30' M
 DST #2 (Lans) 3217-27, Op ¼ hr, R 25' OCM, FSIP 1120#
 RTD 3370, 5¼" @3270, CO 3255, 24/3220-27 (Lans) SSO nat,
 550A, # 5 BOPH/12 hrs, POP, Comp 12-5-51 for IPP, 104 BOPD
 / 10% wtr & was later plugged

NEW INFO: MIRT 8/9/65, CO 3302, 3¼" @ 3296 w/75 ex. GRN log, Pf 3224-28 (Lans)
 250A, Wtr inj. well in Lans 3220-28 (OA) COMPLETED