

TO: STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 207
WICHITA, KANSAS 6720

API Well Number: 15-113-20540-00-01
Spot: NWSWSW Sec/Twnshp/Rge: 24-21S-2W
1032 feet from S Section Line, 5207 feet from E Section Line
Lease Name: J HUXMAN Well #: 1
County: MCPHERSON Total Vertical Depth 3385 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3368		
SURF	8.625	122		

110.01

Well Type: EOR UIC Docket No: E19792.2 Date/Time to Plug: 12/10/2007 12:30 PM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: DOUG WARD Company: AMERICAN ENERGIES CORPORA Phone: (620) 628-4424

Proposed Plugging Method: Sand to 3,315' & top with 4 sxs. cement. Rip casing & pull. Pull casing to 400' & circulate cement to the surface.

Plugging Proposal Received By: MICHAEL WILSON WitnessType: PARTIAL
Date/Time Plugging Completed: 12/10/2007 4:30 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Sanded to 3,293 & topped with 4 sxs. cement. Ripped pipe @ 1,500' & tried to pull same. Casing parted @ 75'. Ran 1" tubing inside 8 5/8" X 4 1/2" casing to 400'. Ran 2 3/8" tubing inside 4 1/2" casing to 400'. Circulated 228 sxs. cement in 8 5/8" X 4 1/2" annulus & inside 4 1/2" casing to the surface. 12/11/2007 - Checked top plug & cement down 80' - Notified operator to top off plug. 01/24/2008 - Ran tubing to 75' & circulated 40 sxs. cement to the surface.

Perfs:

INVOICED
DATE 2-4-08
INV. NO. 200806154

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 30 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POSMIX BY COPELAND ACID & CEMENT. INVOICE #32742. USED 60/40 POSMIX W/4% EGL BY UNITED CEMENTING & ACID COMPANY, INC. INVOICE # 8054.

Plugged through: TBG

District: 02

Signed Michael Wilson
(TECHNICIAN)

PKP