

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-19088-00-00
Spot: SWNESW Sec/Twnshp/Rge: 16-14S-14W
1650 feet from S Section Line, 1650 feet from W Section Line
Lease Name: COADY Well #: 6
County: RUSSELL Total Vertical Depth: 3295 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3195	0	w/unknown sxs cmt

107.09

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/22/2008 2:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TOM Company: AMERICAN WARRIOR, INC. Phone: (620) 275-7461

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/22/2008 3:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Dug out cellar to 11' - did not find any surface pipe.
Perforated at 1575' - 875' - 450'.
Ran tubing to 1604' - pumped 100 sxs 60/40 pozmix - 4% gel cement with 400# hulls.
Pulled to 800' - circulated with 170 sxs cement with 100# hulls.
Dropped 14 joints of tubing down well.
Topped off with 25 sxs cement.

INVOICED
DATE 2-4-08
INV. NO. 20080611SS

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 30 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

JAN 28 2008

16-14-14W
SW NE SW

H B SHUMAKER ESTATE #6 COADY

Contr. AYLWARD DRILLING RUSSELL County

EST

E 1875 RB Comm. Comp. 10-21-60 IP 15 BOPD

E L ^o ops	Depth	Datum
ANH	865	+1010
HEEB	2980	-1105
TOR	3001	-1126
LANS	3040	-1165
SAMPLE TOP		
GRAN WSH	3289	-1414
TD	3295	-1420

Casing
5" 3195

PERF 16/3136-40; 12/3126-29; ACID
1500; SWB 2 BOPH; PLUG; PERF 12/
3081-84; 16/3066-70; ACID 1250;
SWB 6 BOPH, 33% WTR; PERF 12/
3043-47; ACID 1000; SWB 17 BOPH
22% o; SWB 18 BOPH, 33% o (FROM ALL
PERFS) PMP 15 BOPD & 110 BW

HALL GURNEY POOL

R P NIXON, GEO.

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS