

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-21590-00-00
Spot: NW Sec/Twnshp/Rge: 24-24S-32W
3960 feet from S Section Line, 3990 feet from E Section Line
Lease Name: HUSTON Well #: 1-24R
County: FINNEY Total Vertical Depth: 2805 feet

Operator License No.: 32581
Op Name: EXCO RESOURCES, INC.
Address: 12377 MERIT DR STE 1700
DALLAS, TX 75251

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| PROD | 5.5 | 2808 | 0 | WITH 295 SX CMT |
| SURF | 8.625 | 520 | | WITH 250 SX CMT |

91.16

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/10/2008 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JEFF JULIAN Company: EXCO RESOURCES Phone: (214) 368-2084

Proposed Plugging Method: PUMP 300# HULLS & 250 SX CMT DOWN CASING TO FILL TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/10/2008 12:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

BOND LOG TOC @ 670' WITH CONTAMINATED TO 300'. FILL 5 1/2" CASING WITH CMT FROM 2638' TO 0' USING 500# HULLS & 225 SX CMT. PRESSURE TO 400# & HELD. HOOK UP TO 5 1/2" X 8 5/8" ANNULUS & PUMP 30 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2626 | 2638 | | |


INVOICED
DATE 2/8/08
INV. NO. 2008061174

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 04 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed

Ken Jehlik

(TECHNICIAN)

Form CP-2/3

PAT