

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21437-00-00
Spot: N2NESE Sec/Twnshp/Rge: 25-31S-9W
2368 feet from S Section Line, 643 feet from E Section Line
Lease Name: ANTRIM Well #: 1
County: HARPER Total Vertical Depth: 4500 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 904 N LOGAN PO BOX 195
ATTICA, KS 67009

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD | 5.5 | 4497 | | 195 SX |
| SURF | 8.625 | 233 | | 200 SX |

146.25

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/23/2008 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND 50' ABOVE PERFS, 35 SKS 1400', 35 SKS 900', CIRC CMT 285-0'

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 01/23/2008 3:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4340' AND CAPPED WITH 5 SKS OF CMT. THE CASING WAS RECOVERED FROM 3240' AND PULLED TO 1400', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 900' WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED 285' WHERE CMT WAS CIRCULATED TO SURFACE.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4390 | 4400 | | |

INVOICED

DATE 2-4-08
INV. NO. 2008061158

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 30 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING 60/40 POZ 4% GEL

Plugged through: CSG

District: 02

Signed [Signature]
(TECHNICIAN)

[Handwritten initials]