

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21582-00-00
Spot: W2SWSE Sec/Twnshp/Rge: 11-32S-9W
660 feet from S Section Line, 2640 feet from E Section Line
Lease Name: MCDANIEL Well #: 1
County: HARPER Total Vertical Depth: 4840 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 904 N LOGAN PO BOX 195
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4838	3850	25/150 SX CMT.
SURF	8.625	266		190 SX CMT. <u>157.30</u>
T1	2.875	4498		

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 01/25/2008 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTRYE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND BANK 50' ABOVE PERFS. 35 SKS 1400', 35 SKS 900', CIRC. CMT FROM 320-0

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 01/25/2008 8:30 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4262' AND CAPPED WITH 5 SKS OF CMT. THE CASING WAS RECOVERED FROM 3850' AND PULLED TO 1400'. WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 800', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 320', WHERE CMT WAS CIRC. TO SURFACE. THE CASING WAS PULLED AND CMT WAS TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
4404	4412		

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 30 2008
CONSERVATION DIVISION
WICHITA, KS

INVOICED

Remarks: QUALITY OIL WELL CEMENTING #

DATE 2-4-08
INV. NO. 2008061158

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)