

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22526-00-00
Spot: SENENWSE Sec/Twnshp/Rge: 23-11S-25W
2255 feet from S Section Line, 1500 feet from E Section Line
Lease Name: ZEIGLER/HURT Well #: 35-23
County: TREGO Total Vertical Depth: 4100 feet

Operator License No.: 33269
Op Name: CENTRAL OPERATING, INC.
Address: 1600 BROADWAY STE 1050
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	221		

133.25

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/27/2008 9:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: TONY Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE WitnessType: NONE
Date/Time Plugging Completed: 01/27/2008 11:15 AM KCC Agent: BRUCE BASYE

Actual Plugging Report:

1st. Plug at 2115' w/25 sxs.
2nd. Plug at 1190' w/100 sxs.
3rd. Plug at 270' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

INVOICED
DATE 2/8/08
INV. NO. 2008001172

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 01 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Bruce N. Basye

(TECHNICIAN)

PLS