

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-00357-00-00

Spot: NW

Sec/Twnshp/Rge: 28-34S-39W

3960 feet from S Section Line, 3960 feet from E Section Line

Lease Name: ERHARDT

Well #: 1

County: MORTON

Total Vertical Depth: 2750 feet

Operator License No.: 5208

Op Name: EXXONMOBIL OIL CORP

Address: 14950 HEATHROW FORREST PKWY PO
HOUSTON, TX 77210

String Size Depth (ft) Pulled (ft) Comments

L1 5.5 1605 1200

PROD 8.625 2549 700 WITH 100 SX CMT

Box 435 SURF 13 600

89.38

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 12/31/2007 9:00 AM

Plug Co. License No.: 31151

Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DON HORTON

Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 01/08/2008 4:00 PM

KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG RUN TBG TO 2300'. PUMP 400# HULLS & 50 SX CMT. TAGGED TOC @ 2050'. 2ND PLUG RAN TBG TO 630'. PUMP 25 SX CMT. SDON. TAG CMT @ 804'. 3RD PLUG ATTEMPT TO LOAD HOLE WITH 130 BBL MUD & 1000# HULLS. HOLE CIRCULATED. PUMP 25 SX CMT THROUGH TBG @ 630'. TAG CMT TOC @ 590'. 4TH PLUG RAN BOND LOG ON 13". PARTIAL CMT TOC @ 480-75'. RAN TBG TO 590' & PUMP 50 SX CMT. GOOD CIRCULATION. 5TH PLUG PULL TBG TO 40'. PUMP & CIRCULATE CMT TO SURFACE WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2538	2745		
1100	1400		

INVOICED

DATE 2-8-08

INV. NO. 2008061176

RECEIVED
KANSAS CORPORATION COMMISSION


FEB 04 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: TBG

District: 01



Signed

K. Jehlik
(TECHNICIAN)

PRT