

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-00673-00-00  
Spot: NE Sec/Twnshp/Rge: 15-34S-39W  
1320 feet from N Section Line, 1320 feet from E Section Line  
Lease Name: GRABER FEE Well #: 1  
County: STEVENS Total Vertical Depth: 2855 feet

Operator License No.: 5208  
Op Name: EXXONMOBIL OIL CORP  
Address: 14950 HEATHROW FORREST PKWY PO  
HOUSTON, TX 77210 Box 4358

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	8.625	2516	668	WITH 150 SX CMT
SURF	13	600		

92.79

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/09/2008 2:00 PM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/15/2008 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG RUN TBG TO 1859', PUMP 100# HULLS & 50 SX CMT. TAGGED TOC @ 1803'. 2ND PLUG RECOVERED 668' OF 8 5/8". RAN TBG TO 630' & PUMPED 75 SX CMT. TAGGED TOC @ 630'. 3RD PLUG RAN TBG TO 600' & PUMP 25 SX CMT. TAG TOC @ 660'. SDON. 4TH PLUG RAN BOND LOG ON 13" CMT FROM 600' TO 90'. RAN TBG TO 590'. PUMP 400# HULLS IN MUD. PULL 1 JOINT OF TBG & PUMP 25 SX CMT AT 596'. 5TH PLUG WAIT ON CMT FOR 30 MINUTES. PULL TBG TO 560' & PUMP 50 SX CMT. 6TH PLUG TBG TO 30' & PUMP 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2771	2851		
2501	2789		

RECEIVED  
KANSAS CORPORATION COMMISSION  
FEB 04 2008  
CONSERVATION DIVISION  
WICHITA, KS

INVOICED

DATE 2-8-08  
INV. NO. 2008 061176

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: TBG

District: 01

RECEIVED  
JAN 24 2008  
M.D.

Signed

*Ken Jehlik*  
(TECHNICIAN)

Form CP-2/3

*PBT*