

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23676-00-00
Spot: SENESWSE Sec/Twnshp/Rge: 18-10S-18W
720 feet from S Section Line, 1550 feet from E Section Line
Lease Name: VOHS B Well #: 1
County: ROOKS Total Vertical Depth: 3800 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	219		

123.50

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/25/2008 2:00 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: CHUCK RHOADES Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Order 215 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE
Date/Time Plugging Completed: 01/25/2008 5:00 AM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 3755' w/25 sxs.
2nd. Plug at 1625' w/25 sxs.
3rd. Plug at 900' w/100 sxs.
4th. Plug at 275' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

Perfs:


INVOICED
DATE 2-8-08
INV. NO. 2008061178

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 01 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed 
(TECHNICIAN)

JAN 29 2008

