

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21971-00-00
Spot: NESENESE Sec/Twnshp/Rge: 13-7S-18W
1720 feet from S Section Line, 310 feet from E Section Line
Lease Name: CITY OF STOCKTON Well #: 1-13
County: ROOKS Total Vertical Depth: 3360 feet

Operator License No.: 32192
Op Name: PRIDE ENERGY COMPANY, A GENERA
Address: P O BOX 701950
TULSA, OK 74170

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	13.38	89	0	135 SX
PROD	5.5	3359	0	150 SX
SURF	8.625	1284	0	475 SX

109.20

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/23/2008 12:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2943

Proposed Plugging Method: Ordered out 450 sxs 60/40 pozmix - 4% gel - 500# hulls - 15 sxs gel spacer.
Fluid level 100'. No records of cementing 8 5/8" and 5 1/2".
Perforate at 1266'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/23/2008 3:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Log Tech perforated 1266' - two shots per foot.
Ran tubing to 3318' - pumped 15 sxs gel - followed with 40 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 1297' - pumped 100 sxs 60/40 pozmix - 4% gel - circulated cement out 8 5/8".
Shut in and pumped 60 sxs and circulated cement out 5 1/2" casing.
PTOH. Squeezed 60 sxs with 300# hulls down 5 1/2" casing.
Max. P.S.I. 600#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3326	3330		

INVOICED

DATE 2-8-08
INV. NO. 2008061185

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 01 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams


(TECHNICIAN)

Form CP-2/3

JAN 30 2008

PKO

RUPE OIL COMPANY, INC. 13-7-18W
 P.O. BOX 2273 #1-13 CITY OF STOCKTON 1720' FSL &
 WICHITA, KS 67201 310' FEL, SE/4
 CONTR KANDRILCO, INC. CTY ROOKS
 GEOL JIM CRISLER FIELD RIFFE
 ELV 1837 KB SPD 3/11/83 CARD ISSUED 5/26/83 IP P 120 BOPD, NW
1829 GL
 API 15-163-21,971 ARB 3326-3330



SMP	Tops	Depth: Datum
ANH	1266+ 571
TOP	2775- 938
HEEB	2986-1149
TOR	3011-1174
LANS	3030-1193
BKC	3252-1415
ARB	3325-1488
RTD	3360-1523

13 3/8 " COND AT 89/135SX; 8 5/8 " 1284/275SX; 5 1/2 " 3359/150SX
 NO DST'S
 MICT - CO. PF (ARB) 3326-30 W/2 SPF, AC 6 BBLs (15% MCA),
 SWB LD, GSO, POP, P 120 BOPD, NW (GR 24°), 5/3/83

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS