

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-22101-00-00  
Spot: NESWNE Sec/Twnshp/Rge: 13-7S-18W  
1650 feet from N Section Line, 1650 feet from E Section Line  
Lease Name: KORB (C-4) Well #: 1  
County: ROOKS Total Vertical Depth: 3490 feet

Operator License No.: 32192  
Op Name: PRIDE ENERGY COMPANY, A GENERA  
Address: P O BOX 701950  
TULSA, OK 74170

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3489	0	w/150 sxs cmt
SURF	8.625	250	0	w/unknown sxs cmt

113.43

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/25/2008 8:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2943

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 4% gel - 500# hulls - 16 sxs gel spacer.  
Fluid level 650'. No squeeze records - perf anhy.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/25/2008 12:30 PM KCC Agent: RICHARD WILLIAMS

**Actual Plugging Report:**

Perforated anhy 1308'.  
Ran tubing to 3370' - pumped 16 sxs gel - followed with 40 sxs 60/40 pozmix - 4% gel with 200# hulls.  
Pulled tubing to 1375' - pumped 150 sxs cement with 300# hulls - circulated cement - fluid started out 8 5/8".  
PTOH. Allied pumped 40 sxs down 5 1/2" casing - circulated cement out 8 5/8" - shut in 8 5/8".  
Squeezed 5 1/2" with 55 sxs cement.  
Max. P.S.I. 500#. S.I.P. 0#.  
Blew hole in 8 5/8" below head.  
Casing and backside full of cement.

**Perfs:**

Top	Bot	Thru	Comments
3381	3385		

INVOICED

DATE 2-8-08  
INV. NO. 2008061785

RECEIVED  
KANSAS CORPORATION COMMISSION  
**FEB 01 2008**  
CONSERVATION DIVISION  
WICHITA KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams  
(TECHNICIAN)

JAN 30 2008

replacement card

A & M OIL  
STOCKTON KS 67669

13-07S-18W  
NE SW NE

# 1 KORB

site: STOCKTON TWST KS  
contr: CIRCLE M DRILLING

city: ROOKS  
field: RIFFE

API 15-163-22101

well:  
dr date 07/19/83    spd date 07/18/83    drig comp 07/24/83    card issued 02/16/84    last revised 01/01/96


ELV: 1869 GL  
 tops.....depth/datum  
 RTD.....3490 -1621  
 NO TOPS RPTD

IP status:  
 OIL, P 20 BOPD, NW, ARB 3381-3385, 12/01/83  
 INFO RELEASED: 1/1/96 - WAS OIL WELL - TIGHT HOLE  
 CSG: 8-5/8" 250+, 5-1/2" 3489  
 NO CORES OR DSTS RPTD  
 MICT - CO, PF (ARB) 3381-3385 (EST), SO, POP, P 20 BOPD, NW, 12/1/83 - NO OTHER INFO RELEASED BY OPERATOR OR ON KCC RECORDS

COPYRIGHT 1995  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS