

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-1
September 2003

WELL PLUGGING APPLICATION

JAN 24 2008

This Form must be Typed
Form must be Signed
All blanks must be Filled

Please TYPE Form and File ONE Copy

CONSERVATION DIVISION
WICHITA, KS

API # 15 - 163-21971 -00 -00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 3/11/83

Well Operator: Pride Energy Company KCC License #: 32192
(Owner / Company Name) (Operator's)

Address: PO Box 701950 City: Tulsa

State: OK Zip Code: 74170-1950 Contact Phone: (918) 524 - 9200

Lease: City of Stockton Well #: 1-13 Sec. 13 Twp. 7 S. R. 18 East West

SE - NE - SE Spot Location / QQQQ County: Rooks

1720 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

310 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: 13-3/8" Set at: 89 Cemented with: 135 Sacks

Surface Casing Size: 8-5/8" 24# Set at: 1284 Cemented with: 475 Sacks

Production Casing Size: 5-1/2" 14# Set at: 3359 Cemented with: 150 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perfs @ 3326-30' (2 spf)

Elevation: 1882 (G.L. / K.B.) T.D.: 3359 PBTD: N/A Anhydrite Depth: 1266
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Spot 50 sx cmt over perfs, spot gel spacer up to 1266', shoot 5-1/2" csg @ 1266', pump cmt to fill casing to surface. If 5-1/2" is not pulled, pump 100 sx around 5-1/2" and fill to surface.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? No logs available. They were apparently never released by original operator. Memos in Rupe Oil Co. file indicate logs were run and we assume copies were sent to KCC.

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Matthew L. Pride

Phone: (918) 524 - 9200

Address: PO Box 701950 City / State: Tulsa, OK

Plugging Contractor: To be determined Mikes Testing KCC License #: N/A 31529
(Company Name) (Contractor's)

Address: N/A Phone: (N/A)

Proposed Date and Hour of Plugging (if known?): To be determined 1-23/08 12:00

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
Date: 1/21/08 Authorized Operator / Agent: Matthew L. Pride By: Pride Production Co., Inc.
(Signature) Title: General Partner
By: Matthew L. Pride Title: President

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*Well plugged - KCC-blq

Dist
04