

**Notice:** Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117**

Form CP-4  
December 2003  
**Type or Print on this Form**  
Form must be Signed  
All blanks must be Filled

Lease Operator: Hawkins Oil, LLC  
 Address: 427 South Boston Ave. Suite #915, Tulsa, OK 74103  
 Phone: (918) 382-7747 Operator License #: 32693  
 Type of Well: Oil Docket #: N/A  
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
 The plugging proposal was approved on: 6/1/2006 (Date)  
 by: Duane Krueger (KCC District Agent's Name)  
 Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
 Producing Formation(s): List All (If needed attach another sheet)  
Kansas City Limestone Depth to Top: 1994 Bottom: 2004 T.D. 2500  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 015-22194 - 00-00<sup>01</sup>  
 Lease Name: Marsh  
 Well Number: 5-A *ne*  
 Spot Location (QQQQ): -NW - NW - NE  
4950 Feet from  North /  South Section Line  
1650 Feet from  East /  West Section Line  
 Sec. 6 Twp. 26 S. R. 5  East  West  
 County: Butler  
 Date Well Completed: 11/29/1982  
 Plugging Commenced: 11/2/2007  
 Plugging Completed: 11/9/2007

*KCC CP-4  
per CP-4/3*

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle Dolomite	2,447'-2,500'	0	200	8 5/8"	200	0
Kansas City Limestone	1,995'-2,154'	0	2500	4 1/2"	2,500'	1,195'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.  
 11/2/07: Moved in on location. Rigged up to plug bottom. Sanded back to 1,940' dumped 4 sx cement on top of sand with dump bailer. Dug out cellar. Set jacks, worked pipe, shot off 1,195', layed out 4 1/2" pipe. 11/9/2007: Loaded 40 bbls fresh water. rigged up to pump cement. Run 1" down inside surface pipe to 250'  
 Pumped 100 sx cement down 1", filled to surface. Pulled out 1", topped off hole with cement. Washed up, rigged down.

Name of Plugging Contractor: Braiden Petroleum & Well Plugging License #: N/A  
 Address: 10139 SW Haverhill Rd. Augusta, KS 67010

**RECEIVED**  
KANSAS CORPORATION COMMISSION  
**NOV 19 2007**  
CONSERVATION DIVISION  
WICHITA, KS

Name of Party Responsible for Plugging Fees: Hawkins Oil LLC  
 State of Oklahoma County, Tulsa, ss.

James F. Hawkins, JR. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) *James F. Hawkins, Jr.*  
 (Address) 427 S. Boston Ave, Suite #915, Tulsa, OK 74103

**NAN H. WINTON**  
 NOTARY PUBLIC--STATE OF OKLAHOMA  
 TULSA COUNTY  
 My COMMISSION EXPIRES Jun. 21 2011  
 COMMISSION #07006038

and SWORN TO before me this 15th day of November, 20 07  
*Nan H. Winton* My Commission Expires: June 21, 2011  
 Notary Public

*[Handwritten initials]*