

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Hawkins Oil, LLC
Address: 427 South Boston Ave. Suite #915, Tulsa, OK 74103
Phone: (918) 382-7747 Operator License #: 32693
Type of Well: Oil Docket #: N/A
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 6/1/2006 (Date)
by: Duane Krueger (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Kansas City Limestone Depth to Top: 1994 Bottom: 2004 T.D. 2500
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 015-22194 - 00-00
Lease Name: Marsh A
Well Number: 5-A
Spot Location (QQQQ): NE - NW - NE
4950 Feet from North / South Section Line
1650 Feet from East / West Section Line
Sec. 6 Twp. 26 S. R. 5 East West
County: Butler
Date Well Completed: 11/29/1982
Plugging Commenced: 11/2/2007
Plugging Completed: 11/9/2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle Dolomite	2,447'-2,500'	0	200	8 5/8"	200	0
Kansas City Limestone	1,995'-2,154'	0	2500	4 1/2"	2,500'	1,195'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

11/2/07: Moved in on location. Rigged up to plug bottom. Sanded back to 1,940' dumped 4 sx cement on top of sand with dump bailer. Dug out cellar. Set jacks, worked pipe, shot off 1,195', layed out 4 1/2" pipe. 11/9/2007: Loaded 40 bbls fresh water. rigged up to pump cement. Run 1" down inside surface pipe to 250' Pumped 100 sx cement down 1", filled to surface. Pulled out 1", topped off hole with cement. Washed up, rigged down.

Name of Plugging Contractor: Braden Petroleum & Well Plugging License #: N/A
Address: 10139 SW Haverhill Rd. Augusta, KS 67010

Name of Party Responsible for Plugging Fees: Hawkins Oil LLC
State of Oklahoma County, Tulsa, ss.
James F. Hawkins, JR.

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) 427 S. Boston Ave, Suite #915, Tulsa, OK 74103

NAN H. WINTON
NOTARY PUBLIC--STATE OF OKLAHOMA
TULSA COUNTY
My COMMISSION EXPIRES Jun. 21, 2011
COMMISSION #07006038

SUBSCRIBED and SWORN TO before me this 15th day of November, 20 07
My Commission Expires: June 21, 2011