

6050045

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 065- 21,973-00-00

SW SW NE Sec. 16 , T 10 S, R 21 W/E
_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5430

Lease Name Lewis Well # A-1

Operator: Energy Three Inc.
Name & Box 1505
Address Great Bend, Ks. 67530

County Graham

Well Total Depth 3855 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8⁵/₈ feet 250

125.29

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XX

Other well as hereinafter indicated _____

Plugging Contractor Big Three Drilling Company License Number 5836

Address P.O.BOX 52, Gorham, Ks.

Company to plug at: Hour: _____ PM Day: 16th Month: August Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Stan Lovelady

(company name) Energy Three (phone) _____

were: Order 220 sks 50/50 pozmix 6% gel 3% cal. cl., 1 sk flo-cel and 8⁵/₈ " plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs, with

good circulation and no fluid loss.

Signed _____
(TECHNICIAN)

Plugging Operations attended by Agent?: All XX Part _____ None _____

Operations Completed: Hour: 11 PM Day: 16th Month: August Year: 19 84

ACTUAL PLUGGING REPORT

1st plug @ 3830 w/25 sks

2nd plug @ 1730 w/25 sks

3rd plug @ 950 w/100 sks and 1 sk flo-cel

4th plug @ 280 w/40 sks

5th plug @ 40 w/8⁵/₈ " plug 1/2 sk hulls and 10 sks cmt

Remarks: 10 sks in Rat Hole and 10 sks in Mouse Hole

Cemented by Sun Cementing Company

RECEIVED
STATE CORPORATION COMMISSION
08-27-1984
AUG 27 1984

Gil Balthazar-witnessed all of the plugging.

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated
and that I (did/did not) observe this plugging.

Signed Gilbert P. Leiker
(TECHNICIAN)

INVOICED

DATE 8-29-84
INV. NO. 3428

FORM CP-2/3
Rev. 9-82

8-24-84
28