

2 030350

15-173-00195-00-01 #221 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Comp. July, 1959

TECHNICIAN'S PLUGGING REPORT

NE NW 1/4, SEC. 4, T 26 S, R 2 W E

4950' feet from E/S section line

4290' feet from Q/E section line

Operator License # 7439

Lease Name Korber Well # 1-SWD

Operator: Acme Oil Corporation

County Sedgewick 116.71

Name & Address 6235 W. Kellogg

Well Total Depth 3591' feet

Wichita, Ks. 67209

~~Casing~~ Pipe: Size 5 1/2" feet 3472'

Surface Casing: Size 8 5/8" feet 149'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor United Cementing & Acid Co. Inc. License Number \_\_\_\_\_

Address El Dorado, Ks 67042

Company to plug at: Hour: 13:00 Day: 22 Month: 1 Year: 19 86

Plugging proposal received from Leon Bean

(company name) United Cementing Co. (phone) 316-321-4680

were: run 3/4" between 5 1/2" + 8 5/8" to 250' plus pump cement to surface. pump 50 sq. cent down 2 3/8" fiberglass lined tub displace with water, pump 50 sq. cent on top.

2 3/8" fiberglass tub cemented in top 1000' of 5 1/2" casing.

Plugging Proposal Received by Don Thompson  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 18:00 Day: 22 Month: 1 Year: 19 86

ACTUAL PLUGGING REPORT ran 3/4" pipe to 273' between 5 1/2" + 8 5/8" cas.

United # 0499 pumped 85 sq. cent. <sup>37% cc</sup> vice to surface, pulled 3/4" pipe. Pumped 5 sq. gell, 1 sq. bulls, 50 sq. C.H. cement. 27% cc, displace with 45 bbls of water, mixed 75 sq. C.H. cement. 37% cc Pump Press 500# shut well in.

RECEIVED  
STATE CORPORATION COMMISSION  
1/30/86  
JAN 30 1986

CONSERVATION DIVISION  
WICHITA, KANSAS

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

DATE FEB 4 1986

Signed Don Thompson  
(TECHNICIAN)

NO. 12275  
1-22

MAR 07 1986

FORM CP-2/3  
Rev. 01-84