

2 030134

173-20,643-00900

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- unknown

NW NW NW SEC. 1, T 26 S, R 2 E

4950 feet from #1/S section line

4950 feet from #1/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6407

Lease Name Ellist Well # 1

Operator Name Flowers Production Co. Inc.

County Sedgwick

Address 129 N. Emporia

Well Total Depth 2911 94.61 feet

Eldorado, Ks. 67042

~~Casing~~ Pipe: Size 5 1/2" feet 2908'

Surface Casing: Size 8 5/8" feet 220'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Towanda Well Service License Number 5683

Address Hwy 254, Towanda, Ks. 67144

Company to plug at: Hour: 9:30 Day: 31 Month: 8 Year: 1984

Plugging proposal received from Lewis Wilson

(company name) Towanda Well Service (phone) _____

were: Perf. 2839' to 2844' wireline plug 2864' C.T.B.P. 2790'
dump 5 cu. cent. / bailer, shoot and pull csg., set top bridge
275', dump redi-mix to surface.

Plugging Proposal Received by Stan Marcotte, Dist # 2
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 AM Day: 31 Month: 8 Year: 1984

ACTUAL PLUGGING REPORT Set C.T.B.P. at 2790', dumped 3 cu. cent. / bailer
shot + pulled 2008' 5 1/2" csg., set top bridge 250' to 240'
Knebler Concrete Supply # 16401 dumped 4 yds. redi-mix
to top of 8 5/8" sur. csg.

RECEIVED
STATE CORPORATION COMMISSION
9-10-84
SEP 10 1984

Remarks: _____ (if additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-17-84

Signed Don Thompson
(TECHNICIAN)

INV. NO. 3707
8-31

OCT 03 1984