


State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 7 1973
2-7-1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. D. B. Pulley of Rockhold Engineering, Inc., has this date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Incorporated,

Complete Address: Box #352, Great Bend, Kansas.

Lease Name: Montgomery Well No. 3

Location: CNE Sec. 8 Twp. 8 Rge. (E)(W) 23

County: Graham Total Depth 3765' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Pulley was instructed to plug the well as follows:

166'--8 5/8" Surface casing, cement circulated with 125 Sx.
3764'--5 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to 3741'. Top of perforations @ 3595'.

Push plug to 3550' sand from 3550' to 3525' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

N. S. Nichole
Conservation Division Agent