

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 7 1973
2-7-1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. D. B. Pulley of Rockhold Engineering, Inc., has this date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Incorporated,

Complete Address: Box #352, Russell, Kansas.

Lease Name: Montgomery Well No. 2

Location: CS/2-S/2-NE Sec. 8 Twp. 8 Rge. (E)(W) 23

County: Graham Total Depth 3739' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Pulley was instructed to plug the well as follows:

166'--8 5/8" Surface casing, cement circulated with 125 Sx.

3740'--5 1/2" Casing cemented on bottom with 100 Sx. Well plugged back to 3740'. Top of perforations- 3536' to 3540'.

Push plug to 3500', sand back from 3500' to 3460' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 25 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

H. L. Deibel
Conservation Division Agent