

State of Kansas



JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

DEC 8 1964  
12-8-1964  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Bob Barnes of Barnes & Sons Pipe Pulling has this

date requested permission to plug the following described well:

Fender Pipe & Supply, Inc.

Mr. Barnes guarantees payment of the plugging fee.

Operator's full Name: Fender Pipe & Supply, Incorporated,

Complete Address: Box # 202, Russell, Kansas.

Lease Name: Ellsworth Well No. B-3

Location: SE-NE-SE Sec. 8 Twp. 8 Rge. (E) (W) 23

County Graham Total Depth 3730 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Barnes was instructed to plug the well as follows:

154'--8 5/8" Surface pipe, cement circulated with 115 Sx.  
3729'--5 1/2" Production casing cemented with 75 Sx.

Sand well back to 3720' and 5 Sx. cement with dump bailer.  
Pull 5 1/2" to 600' and circulate heavy gel mud, pull 5 1/2" to 540  
and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2" to 150' and dis-  
place 20 Sx. cement thru 5 1/2". Pull 5 1/2", set bridge @ 30' and  
10 Sx. cement to bottom of cellar.

Very truly yours,

M. L. Nichols  
Conservation Division Agent