

15-065-01009-00-00

State of Kansas



FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAY 1 1964

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Albert Schiffner of Forbes Casing Pulling Co., has this date requested permission to plug the following described well:
John O. Farmer, Inc.,
Mr. Schiffner guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Incorporated,

Complete Address: 370 W. Wichita, Russell, Kansas.

Lease Name: Ellsworth Well No. A A-1

Location: SE-NW-NE Sec. 17 Twp. 8 Rge. (E) (W) 23

County Graham Total Depth 3674 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Schiffner was instructed to plug the well as follows:

163'--8 5/8" Surface pipe, cement circulated with 110 Sx.
3674'--5 1/2" production casing cemented with 100 Sx. Well plugged back to 3528'. Top perforations @ 3423'.

Sand well back to 3410' and set 5 Sx. cement with dump bailer.
Pull 5 1/2" to 600' and circulate heavy gel mud. Pull 5 1/2" to 540' and displace 20 Sx cement thru 5 1/2". Pull 5 1/2" to 180' and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2", set bridge @ 30' and 10 Sx. cement to bottom of cellar.

Very truly yours,

W. L. Nichols