

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Larry Langhoper of Big Three Drilling has this date requested permission to plug the following described well:

Operator's Full Name: Energy Three Inc.

Complete Address: P.O. Box 1505 St. Bend, Ko. 67530

Lease Name: Justus - Wyatt Well No. 1

Location: SE-SE-SE Sec. 6 Twp. 8 Rge. 23 (E) (W)

County: Graham Total Depth: 3800'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: Wash Down

Mr. Langhoper was instructed to plug the well as follows:

8 5/8" @ 254' w/185 ax. original T.D. 3765' -
Plugged 2-23-81 w/70 ax @ 900'; 20 ax @ 240'; 10 ax
@ 40'; 50 ax in rat hole; 5 ax in mousehole. Hard
cement found at 0-42' → 240-310' → 875'-975'; New Plug
50 permix 4% gel - 3% cc + 8 5/8 plug; spot 70 ax @
900; 40 ax @ 240'; 10 ax @ 40' - 0 on bridge; 10 ax in rat
hole; 5 ax in mouse hole;

Very truly yours,

Remond L. Hamel
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
MAY 7 1982
5-7-1982
CONSERVATION DIVISION
Wichita, Kansas