

State of Kansas



FORM CP-2

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Dave Cromeau of Brown Drilling Inc has this date requested permission to plug the following described well:

Operator's Full Name: Griggs Oil Company Inc

Complete Address: 1625 Viking N.S.B. & T Bldg Wichita, Kans.

Lease Name: Montgomery Well No. # 2

Location: 330-5 NE-NE-NE Sec. 7 Twp. 8^S Rge. 23^W (E) (W)

County: Graham Total Depth: 3790^{FE}

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Cromeau was instructed to plug the well as follows:

8 5/8" - 274^{FE} SP. CUC w/ 156ST Cement - 2% Gel - 3% Ca-Cl₂
Order 125ST 5/8" Forming 4% Gel - 3% Ca-Cl₂ + 8 5/8" Plug.

Spot with Drill Stem - With Heavy Mud Between all Plugs

- 1ST Plug @ 990^{FE} w/ 70ST Cement
- 2ND Plug @ 270^{FE} w/ 40ST Cement
- 3RD Plug - Solid Bridge - w/ 40^{FE} 1/2" Cement
- 5TH In Rat Hole

Very truly yours, By Allied Ent

Marion Schmidt
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
NOV 30 1981 11-30-1981
CONSERVATION DIVISION
Wichita, Kansas