

State of Kansas



15-065-02981-00-10

FORM - GP-2
Rev. 9-8-64

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 26 1964

CONSERVATION DIVISION
Wichita, Kansas

10/26/64

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Russell Hoberecht of Ace Pipe Pulling Co., has this

date requested permission to plug the following described well:

Leo J. Dreiling Oil Co.,

Mr. Hoberecht guarantees payment of the plugging fee.

Operator's full Name: Leo J. Dreiling Oil Company,

Complete Address: Victoria, Kansas.

Lease Name: Higer Well No. B-2

Location: C $\frac{1}{2}$ -NE-NE Sec. 19 Twp. 8 Rge. (E) (W) 23

County Graham Total Depth 3745 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Hoberecht was instructed to plug the well as follows:

187'--8 5/8" Surface pipe cement circulated with 150 Sx.

3745'--5 1/2" production casing cemented with 100 Sx. Well
plugged back to 3717'. Top perforations @ 3681'.

Sand well back to 3670' and set 5 Sx. cement with dump bailer.
Pull 5 1/2" casing to 600' and circulate heavy gel mud. Pull 5 1/2"
to 540' and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2" to 180'
and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2", set rock
bridge @ 35' and 10 Sx. cement to bottom of cellar.

Very truly yours,

A. L. Nichols

Conservation Division Agent