



15-065-02977-00-08

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 11 1971  
CONSERVATION DIVISION  
Wichita, Kansas

1/11/71

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Darrell Kelso of Knight Casing Pulling Co., Inc has this date requested permission to plug the following described well:

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: J. K. Fortner

Complete Address: Box #97, Ellinwood, Kansas.

Lease Name: Bethell Well No. X 2 *WHM REC 10/3/65*

Location: NE-SW-NE Sec. 17 Twp. 8 Rge. (E)(W) 23

County: Graham Total Depth 3675' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Kelso was instructed to plug the well as follows:

170'--8 5/8" Surface casing, cement circulated.

3675'--5 1/2" Production casing cemented on bottom with 100 Sx. Well plugged back to 3450', Top perforations @ 3394'.

Sand well back to 3350' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Sx. cement, staged.

Very truly yours,

*M. L. Dickels*

Conservation Division Agent