



15-065-02978 - 00-00

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 12 1971  
CONSERVATION DIVISION  
Wichita, Kansas

1/12/71

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Darrell Kelso of Knight Csg. Pulling Co., Inc. has this date requested permission to plug the following described well:

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: J. K. Fortner

Complete Address: Box #97, Ellinwood, Kansas.

Lease Name: Bethell Well No. 4

Location: SE-SE-NE Sec. 17 Twp. 8 Rge. (E)(W) 23

County: Graham Total Depth 3602' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Kelso was instructed to plug the well as follows:

178'--8 5/8" Surface casing, cement circulated with 135 Sx.  
3591'--5 1/2" Production casing cemented on bottom with 100 Sx. Well  
plugged back to 3407' Top perforations from 3393' to 3396'.

Sand well back to 3375' and set 5 Sx. cement with dump bailer. Pull 5 1/2"  
casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Sx.  
cement, staged.

Very truly yours,

*A. L. Nichols*  
Conservation Division Agent