



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

FEB 11 1963

CONSERVATION DIVISION
 Wichita, Kansas

2/11/63

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Russell Hoberecht of Ace Pipe Pulling Co has this

date requested permission to plug the following described well:

Mr. Hoberecht guarantees payment of the plugging fee.

Leo J. Dreiling Oil Co
 Operator's full Name: Leo J. Dreiling Oil Co.

Complete Address: Victoria, Kansas

Lease Name: Ellsworth Well No. 1

Location: CE $\frac{1}{2}$ -W $\frac{1}{2}$ -NW Sec. 17 Twp. 8 Rge. (E) (W) 23

County Graham Total Depth 3710 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Hoberecht was instructed to plug the well as follows:

1 $\frac{1}{2}$ " Tubing sanded in and parted @ 900', (To be abandoned).

Circulate heavy gel mud @ 900', pull casing to 650', cir-

culate heavy gel mud and displace 20 Sx cement thru 5 $\frac{1}{2}$ " csg.

Pull casing to 190' and displace 20 Sx cement thru Casing.

Pull casing, set bridge and 10 Sx cement to bottom of cellar.

Very truly yours,

W. L. Nichol
 Conservation Division Agent