



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 8 1963

CONSERVATION DIVISION
Wichita, Kansas

2/8/63

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Russle Hoberecht of Ace Pipe Pulling Co has this

date requested permission to plug the following described well:
Hoberecht

Mr. Leo J Dreiling Oil Co guarantees payment of the plugging fee.

Operator's full Name: Leo J. Dreiling Oil Co

Complete Address: Victoria, Kansas.

Lease Name: Ellsworth Well No. 2

Location: SW-NW-NW Sec. 17 Twp. 8 Rge. (E) (W) 23

County Gr_ham Total Depth 3685 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Hoberecht was instructed to plug the well as follows:

Sand well back to 3540', set 4 Sx cement w/dump bailer.

Pull casing to 550', circulate with heavy mud (20nSx Gel)

Displace 20 Sx cement thru 5 1/2" @ 550'. Heavy mud to 180'

displace 20 Sx ce,emt thru 5 1/2". Pull pipe set plug @ 40 ft

with 10 Sx cement to bottom of cellar.

Very truly yours,

H. L. Fuchs
Conservation Division Agent