



15-065-02980-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 3 1964

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

11/3/64
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Russell Hoberecht of Ace Pipe Pulling Co., has this

date requested permission to plug the following described well:

Leo J. Dreiling

Mr. Hoberecht guarantees payment of the plugging fee.

Operator's full Name: Leo J. Dreiling Oil Company,

Complete Address: Victoria, Kansas.

Lease Name: Higer Well No. A-2

Location: SW-NW-NW Sec. 20 Twp. 8 Rge. (E) (W) 23

County Graham Total Depth 3730 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Hoberecht was instructed to plug the well as follows:

199'--8 5/8" Surface pipe, cement circulated with 120 Sx.
3729'--5 1/2" Production casing cemented with 100 Sx. Well plugged
back to 3719. Top perforations @ 3440. Well two-staged from
1922' to surface.
Squeeze well with gel from perforations to 640'. 10 Sx. cement
from 640 to 560'. 2 Sx. gel from 560' to 320' and 40 Sx. cement
from 320' to bottom of cellar.

Very truly yours,

Conservation Division Agent