

State of Kansas



15-065 20070-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 9 1967

CONSERVATION DIVISION
Wichita, Kansas

8/9/67

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bob Miller of L. J. Dreiling & Sons, Inc., this date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: John P. Jennings,

Complete Address: 412 Union Center, Wichita, Kansas.

Lease Name: McFadden Est. Well No. 1

Location: NE-SE-NE Sec. 23 Twp. 8 Rge. (E)(W) 23

County Graham Total Depth 3615 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Miller was instructed to plug the well as follows:

161'--8 5/8" Surface pipe, cement circulated with 150 Sx. Dakota section from 1300' to 1515'.

Circulate hole with heavy mud, Pull DP to 1525' and dis-
place 100 Sx. cement thru DP. Pull DP to 180' and displace
20 Sx. cement thru DP. Pull DP, set bridge with 1/2 sack hulls
and 10 Sx. cement to cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent