

State of Kansas



15-065-19015-00-00

FORM - CP-2  
Rev. 9-8-64

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

11/3/64  
RECEIVED  
STATE CORPORATION COMMISSION  
NOV 3 1964  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Russell Hoberecht of Ace Pipe Pulling Co. has this

date requested permission to plug the following described well:

Leo J. Dreiling  
Mr. Hoberecht guarantees payment of the plugging fee.

Operator's full Name: Leo J. Dreiling Oil Company,

Complete Address: Victoria, Kansas.

Lease Name: Higer Well No. A-1

Location: SW-SW-NW Sec. 20 Twp. 8 Rge. (E) (W) 23

County Graham Total Depth 3760 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Hoberecht was instructed to plug the well as follows:

185'---8 5/8" Surface pipe, cement circulated with 120 Sx.  
3755'---5 1/2" Production casing cemented with 125 Sx. Well plugged  
back to 3745. Top perforation @ 3696.

Sand well back to 3865' and set 5 Sx. cement with dump bailer.  
Pull 5 1/2" to 500' and circulate heavy gel mud. Pull 5 1/2" to 440'  
and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2" to 180' and dis-  
place 20 Sx. cement thru 5 1/2". Pull 5 1/2", set bridge @ 30' and  
10 Sx. cement to bottom of cellar.

Very truly yours,

*M. L. J. [Signature]*

Conservation Division Agent