

15-065-01318-00-00

Form CP-3
Rev. 6-4-68

4

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAY 24 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name John O. Farmer, Incorporated,
Complete Address Box #352, Russell, Kansas.
Lease Name Mickelson Well No. C-1
Location SE-SW-NE Sec. 27 Twp. 8 Rge. (E) (W)22
County Graham Total Depth 3785'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Ralph Comstock Pipe Pulling, Incorporated,
Address 320 South Park, Stafford, Kansas. License No. 490
Operation Completed: Hour 1:00 PM Day 17 Month 5 Year 1971

The above well was plugged as follows:

165'--8 5/8" Surface casing, cement circulated.
3761'--5 1/2" Production casing cemented on bottom. Well plugged back to 3580'. Top perforations @ 3502'.
Sanded well back to 3490' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing and squeezed well initially with 4 sacks hulls and 5 sacks gel and followed with 90 Sx. cement from 950' to 650' then 10 Sx. gel from 650' to 200', followed with 1 sack hulls from 250' to 200' and finally 60 Sx. cement from 200' to bottom of cellar. Maximum pump-in pressure-300#. Final shut-in pressure-100#. (Mudding and cementing operations performed by Allied Cementing Co., Inc.).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *N. L. Dickols*
Well Plugging Supervisor

DATE 5-24-71
INV. NO. 3737-12