

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

REC'D
8-28-69

15-065-20253-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Three "G" Oil, Incorporated.

Complete Address 1101 Wichita Plaza Building, Wichita, Kansas.

Lease Name Lovelady Well No. 1

Location NW-NW-SE Sec. 1 Twp. 8 Rge. (E) (W) 23

County Graham Total Depth 3685'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Leben Drilling, Incorporated.

Address Box #486, Great Bend, Kansas. License No. _____

Operation Completed: Hour 9:00 PM Day 16 Month 8 Year 1969

The above well was plugged as follows:

210'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 850'.

Circulated hole with heavy mud. Pulled DP to 1050' and displaced 100 Sx. cement thru
DP from 1050' to 725'. Pulled DP to 250' and displaced 20 Sx. cement thru DP from
250' to 190'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. R. Nichols
Well Plugging Supervisor

DATE 8-18-69
INV. NO. 325-w