

KANSAS

*Handwritten mark*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 18 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
*July 18<sup>th</sup>, 1969*

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Herndon Drilling Company,

Complete Address P. O. Box #489, Tulsa, Oklahoma.

Lease Name Pembleton Well No. 1

Location CS/2-S/2-SW/4 Sec. 2- Twp. 8 Rge. (E) (W) 23

County Graham Total Depth 3730'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  X

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Sage Drilling Company, Incorporated,

Address 500 Bitting Building, Wichita, Kansas. License No. \_\_\_\_\_

Operation Completed: Hour 8:30 PM Day 10 Month 7 Year 1969

The above well was plugged as follows:

217' - 8 5/8" Surface casing, cement circulated with 175 Sx.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 100 Sx. cement thru

DP from 1200' to 875'. Pulled DP to 250' and displaced 20 Sx. cement thru DP from 250'

to 190'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of

cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *N. L. Dehok*  
Well Plugging Supervisor

DATE 7/18/69

INV. NO. 111-w