

KANSAS

48

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAY 24 1971
CONSERVATION DIVISION
Wichita, Kansas

5-24-71

Operator's Full Name John O. Farmer, Incorporated,

Complete Address Box #352, Russell, Kansas.

Lease Name Mickelson Well No. C-2

Location NW-SE-NE Sec. 27 Twp. 8 Rge. (E) (W) 22

County Graham Total Depth 3797'

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated

Plugging Contractor Ralph Comstock Casing Pulling, Incorporated,

Address 320 South Park, Stafford, Kansas. License No. 490

Operation Completed: Hour 3:30 PM Day 17 Month 5 Year 1971

The above well was plugged as follows:

165'---8 5/8" Surface casing, cement circulated.
3715'---5 1/2" Casing cemented on bottom. No plug back indicated, top perforations @ 3504'.
No attempt to salvage 5 1/2" casing.
squeezed 5 1/2" casing with initially 1 sack hulls and 25 cement and followed with 24 sacks
gel from 3500' to 950' then 1 sack hulls from 950' to 850' and finally 80 Sx. cement
from 850' to bottom of cellar. Maximum pump-in pressure-300#. Final shut-in pressure-
100#. Squeezed annulus with 150 Sx. cement. Maximum pump-in pressure-300#. Final
shut-in pressure-50#. (Mudding and cementing by Allied Cementing Co., Inc.).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. L. Nichols
Well Plugging Supervisor

DATE 5-24-71

INV. NO. 2738-10