

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE NE SW

SEC. 27 TWP. 8 RGE. 22 ✓

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Hocker

Operator Carter Oil Co Address Box 786 Great Bend, Kans

Field _____ County Graham

Total Depth 5777 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 211' circulated with cement - 5 1/2" at 3700' with
125 sax cement behind.

Filled with chat to 3750', set 4 sax cement with dump bailer,
pulled 1500' 5 1/2" - filled with mud to 210', set rock and 10 sax
cement - mud to 35', set rock and 10 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION

JAN 24 1953
JAN 24 1953
CONSERVATION DIVISION
Wichita, Kansas

Robert J. Fry
District Conservation Agent

Date 1-23-53

PLUGGING
FILE SEC. 27 8 - R 22
BOOK PAGE 75 LINE 14